

TAR HEEL RAILROAD CONSTRUCTION CO., INC.

P.O. BOX 11426

WINSTON-SALEM, NORTH CAROLINA 27116-1426

MARTIN K. DeBRUHL
President

MAX W. DeBRUHL, III
Vice President

Michael Reed
Guilford County
NE park

January 4, 2017

- CONSTRUCTION
- DEMOLITION
- REHABILITATION

Mr. Reed,

Tar Heel Railroad Construction Co., Inc. is pleased to offer you the following quote for your railroad track maintenance. All labor, equipment, materials and supervision are included. The following scope of work is included.

1. Blow the leaves off track.
2. Tighten all bolts.
3. Adjust gauge as needed to 24.25" in straight runs. 1/8" allowance.
4. Adjust gauge as needed to 24.5" in curves-1/8" allowance.
5. Grind all joints which have mismatched heads.
6. Restore one frog by welding.
7. Remove loose gauge rods which are welded to the rails.
8. Furnish and install gauge rods to curve (approx. 50) as needed to include threaded rod, flat washers and nuts.

Our price to complete this scope of work is \$15,970.00. All workmanship and labor shall be warranted for ninety days. In addition, we will include an inspection (at no charge) of the track on the sixth month, ninth month, and twelve month anniversary of completion of the work.

Thank you for the opportunity to be of service.

Sincerely,



Marty DeBruhl

Terms Net 30